



plumbers

Risk controls for handling roof sheeting

Before applying a new risk control, review its use to ensure it does not introduce new risks during the tasks.

- Where practicable have sheets craned directly onto the roof.
- Ensure a clear compacted surface around the building perimeter.
- Have sheets craned onto trestles or other support at waist height.
- Ensure sheets are stacked appropriately when placed at the site.
- A minimum of two persons to handle large sheets to roof area and a minimum of two persons to lift and place on the roof.
- Use safe manual handling techniques.
- Undertake a TAKE 5: Ensure you are awake, focused, warmed up and ready to undertake the tasks required.

